

# STANDARD SPECIFICATIONS

for

## ROAD, DRAIN & SEWER CONSTRUCTION



Approved & Adopted  
July, 2011

# STANDARD SPECIFICATIONS

for

## ROAD, DRAIN & SEWER CONSTRUCTION



Approved & Adopted  
July, 2011

By: Manchester Highway Commission  
Raymond Hebert, Chairman

Harold Sullivan, Vice Chairman  
Robert R. Rivard, Clerk

Rick Rothwell, Commissioner  
Bill Skouteris, Commissioner

Kevin A. Sheppard, P.E., Director of Public Works  
Timothy J. Clougherty, Deputy Director of Public Works

## **PREFACE**

The State of New Hampshire, Department of Transportation Standard Specifications for Road and Bridge Construction have been used as the basis for the specifications herein contained. They have been edited and adapted to suit the needs and requirements of the Department of Highways. Several sections have been duplicated in their entirety.

These specifications are intended to relay to developers, contractors and other builders and trades, information concerning the Department of Highways' requirements relative to all construction under its jurisdiction in the City of Manchester, New Hampshire. To facilitate this end, the Standard Specifications have been divided into four parts as follows:

### **PART I – DEFINITIONS AND TERMS**

Part I of the Standard Specifications lists and defines several terms found throughout the specifications.

### **PART II – PUBLIC IMPROVEMENTS**

Part II of the Standard Specifications outlines the Department's requirements concerning public improvements included in site development and subdivision projects. These requirements shall also apply to off-site improvements conducted within streets, rights-of-way, easements or other public lands belonging to the City of Manchester, New Hampshire.

All work relative to the above shall be conducted according to Section V of this part and the Technical Specifications as outlined in Part III.

### **PART III – CONTRACT GENERAL PROVISIONS**

Part III of the Standard Specifications outlines the Department's contractual requirements concerning work for road, drain and sewer projects along with other related work. These requirements shall apply to all such work contracted by the City of Manchester, Department of Highways and shall be considered a part of all proposals.

### **PART IV – TECHNICAL SPECIFICATIONS**

Part IV of the Standard Specifications outlines the Department's detailed requirements concerning the control of material, rules of construction and basis of payment. Supplemental Specifications not yet considered standard and Special Provisions for explaining items of work unique to a specific project, will be included in the proposal forms prepared by the Department.

The sections included in this part along with any Supplemental Specifications and Special Provisions, shall be considered a part of all proposals.

**STANDARD SPECIFICATIONS  
For  
ROAD, DRAIN & SEWER  
CONSTRUCTION**

**TABLE OF CONTENTS**

**PART I -- DEFINITIONS AND TERMS**

| <b><u>Section</u></b>        | <b><u>Page</u></b> |
|------------------------------|--------------------|
| <b>Definitions and Terms</b> | <b>I - 1</b>       |

**PART II -- PUBLIC IMPROVEMENTS**

|          |                                       |                |
|----------|---------------------------------------|----------------|
| <b>1</b> | <b>General Requirements</b>           | <b>II - 1</b>  |
| <b>2</b> | <b>Roadway Requirements</b>           | <b>II - 4</b>  |
|          | 2.1 General                           | II - 4         |
|          | 2.2 Horizontal Alignment              | II - 4         |
|          | 2.3 Vertical Alignment                | II - 5         |
|          | 2.4 Cross Sections                    | II - 5         |
|          | 2.5 Driveways                         | II - 5         |
| <b>3</b> | <b>Sewer Requirements</b>             | <b>II - 10</b> |
|          | 3.1 General                           | II - 10        |
|          | 3.2 Horizontal Alignment              | II - 10        |
|          | 3.3 Vertical Alignment                | II - 10        |
|          | 3.4 Pump Stations                     | II - 12        |
|          | 3.5 Forcemains                        | II - 15        |
| <b>4</b> | <b>Storm Drainage Requirements</b>    | <b>II - 11</b> |
|          | 4.1 Calculations                      | II - 15        |
|          | 4.2 Drainage Pipe                     | II - 15        |
|          | 4.3 Drainage Structures               | II - 16        |
|          | 4.4 Detention Basins                  | II - 17        |
| <b>5</b> | <b>Street Excavation Requirements</b> | <b>II - 18</b> |
|          | 5.1 General                           | II - 18        |
|          | 5.2 Inspection Fees and Requirements  | II - 18        |

|          |                                                                                          |                |
|----------|------------------------------------------------------------------------------------------|----------------|
| 5.3      | Encumbrances and Traffic Control                                                         | II - 20        |
| 5.4      | Protection of Work Area                                                                  | II - 21        |
| 5.5      | Proof of Compliance                                                                      | II - 21        |
| 5.6      | Paving Policy                                                                            | II - 21        |
| 5.7      | Street Restoration and Patching Guidelines                                               | II - 23        |
| 5.8      | Insurance Requirements                                                                   | II - 26        |
| 5.9      | Emergency Provisions                                                                     | II - 26        |
| 5.10     | Street Excavation General Instructions                                                   | II - 27        |
| 5.11     | Winter Excavation Permits                                                                | II - 29        |
| <b>6</b> | <b>General Provisions for Construction of Public Improvements</b>                        | <b>II - 36</b> |
| 6.1      | Scope of Work                                                                            | II - 36        |
| 6.2      | Control of Work                                                                          | II - 36        |
| 6.2.1    | Authority of the Engineer                                                                | II - 36        |
| 6.2.2    | Plans and Working Drawings                                                               | II - 36        |
| 6.2.3    | Conformity with Plans and Specifications                                                 | II - 37        |
| 6.2.4    | Coordination of Specifications, Supplemental Specification, Plans and Special Provisions | II - 37        |
| 6.2.5    | Cooperation by Contractor                                                                | II - 38        |
| 6.2.6    | Cooperation with Utilities                                                               | II - 38        |
| 6.2.7    | Construction Stakes, Lines and Grades                                                    | II - 38        |
| 6.2.8    | Authority and Duties of Representatives of the Engineer                                  | II - 38        |
|          | <b>INSPECTION SERVICES</b>                                                               | <b>II - 39</b> |
| 6.2.9    | Inspection Agreement                                                                     | II - 39        |
| 6.2.10   | Inspection of Work                                                                       | II - 39        |
| 6.2.11   | Removal of Unacceptable and Unauthorized Work                                            | II - 40        |
| 6.2.12   | Maintenance During Construction                                                          | II - 40        |
| 6.2.13   | Failure to Maintain Work                                                                 | II - 40        |
| 6.2.14   | Acceptance                                                                               | II - 40        |
| 6.3      | Control of Material                                                                      | II - 41        |
| 6.3.1    | Source of Supply and Quantity Requirements                                               | II - 41        |
| 6.3.2    | Samples, Tests, Cited Specifications                                                     | II - 41        |
| 6.3.3    | Certificates of Compliance                                                               | II - 42        |
| 6.3.4    | Plant Inspection                                                                         | II - 43        |
| 6.3.5    | Storage of Materials                                                                     | II - 43        |
| 6.3.6    | Handling Materials                                                                       | II - 43        |
| 6.3.7    | Unacceptable Materials                                                                   | II - 43        |
| 6.3.8    | Disposal of Surplus and Waste Materials                                                  | II - 43        |
| 6.4      | Legal Relations and Responsibility to Public                                             | II - 43        |

|        |                                                               |         |
|--------|---------------------------------------------------------------|---------|
| 6.4.1  | Laws to be Observed                                           | II – 43 |
| 6.4.2  | Permits, Licenses and Taxes                                   | II – 44 |
| 6.4.3  | Restoration of Surfaces Opened by Permit                      | II – 44 |
| 6.4.4  | Sanitary, Health and Safety Provision                         | II – 44 |
| 6.4.5  | Public Convenience and Safety                                 | II – 45 |
| 6.4.6  | Railway-Highway Provisions                                    | II – 45 |
| 6.4.7  | Construction Over or Adjacent to Navigable Waters             | II – 46 |
| 6.4.8  | Barricades and Warning Signs                                  | II – 46 |
| 6.4.9  | Protection and Restoration of Property and Landscape          | II – 46 |
| 6.4.10 | Contractor's Responsibility for Work                          | II – 47 |
| 6.4.11 | Contractor's Responsibility for Utility Property and Services | II – 47 |
| 6.4.12 | Personal Liability of Public Officials                        | II – 48 |
| 6.4.13 | Environmental Protection                                      | II – 49 |

## **6.5 Prosecution and Progress** II – 49

|       |                                                       |         |
|-------|-------------------------------------------------------|---------|
| 6.5.1 | Subletting or Work                                    | II – 49 |
| 6.5.2 | Prosecution and Progress                              | II – 49 |
| 6.5.3 | Limitation of Operations (Night/ Sunday/Holiday Work) | II – 49 |
| 6.5.4 | Character of Workmen                                  | II – 49 |
| 6.5.5 | Methods and Equipment                                 | II – 50 |

## **PART III -- CONTRACT GENERAL PROVISIONS**

|            |                                                                 |                |
|------------|-----------------------------------------------------------------|----------------|
| <b>101</b> | <b>Bidding Requirements and Conditions</b>                      | <b>III – 1</b> |
| 101.01     | Prequalification of Bidders                                     | III – 1        |
| 101.02     | Contents of Proposals                                           | III – 1        |
| 101.03     | Issuance of Proposals                                           | III – 1        |
| 101.04     | Interpretation of Quantities in the Bid Schedule                | III – 2        |
| 101.05     | Examination of Plans, Specifications, Proposal and Site of Work | III – 3        |
| 101.06     | Familiarity of Laws                                             | III – 4        |
| 101.07     | Preparation of Bids                                             | III – 4        |
| 101.08     | Irregular Bids                                                  | III – 5        |
| 101.09     | Bid Guaranty                                                    | III – 5        |
| 101.10     | Delivery of Bids                                                | III – 6        |
| 101.11     | Withdrawal of Bids                                              | III – 6        |
| 101.12     | Combination of Proposals                                        | III – 6        |
| 101.13     | Public Opening of Bids                                          | III – 6        |
| 101.14     | Disqualification of Bids                                        | III – 4        |
| <b>102</b> | <b>Award and Execution of Contract</b>                          | <b>III – 8</b> |

|            |                                                                                                           |          |
|------------|-----------------------------------------------------------------------------------------------------------|----------|
|            | 102.01 Consideration of Bids                                                                              | III – 8  |
|            | 102.02 Award of Contract                                                                                  | III – 8  |
|            | 102.03 Cancellation of Award                                                                              | III – 8  |
|            | 102.04 Return of Bid Guaranty                                                                             | III – 8  |
|            | 102.05 Requirement of Contract Bonds                                                                      | III – 8  |
|            | 102.06 Execution and Approval of Contract                                                                 | III – 9  |
|            | 102.07 Failure to Execute Contract                                                                        | III – 9  |
| <b>103</b> | <b>Scope of Work</b>                                                                                      | III – 10 |
|            | 103.01 Intent of Contract                                                                                 |          |
|            | 103.02 Differing Site Conditions, Suspensions of Work and<br>Significant Changes in the Character of Work | III – 10 |
|            | A. Differing Site Conditions                                                                              | III – 10 |
|            | B. Suspensions of Work                                                                                    | III – 10 |
|            | C. Significant Changes in Character of Work                                                               | III – 11 |
|            | 103.03 Extra Work                                                                                         | III – 12 |
|            | 103.04 Maintenance of Traffic                                                                             | III – 12 |
|            | 103.05 Rights In and Use of Materials Found on the Project                                                | III – 12 |
|            | 103.06 Final Cleaning Up                                                                                  | III – 13 |
|            | 103.07 Value Engineering Proposals by Contractor                                                          | III – 13 |
| <b>104</b> | <b>Control of the Work</b>                                                                                | III – 17 |
|            | 104.01 Authority of Engineer                                                                              | III – 17 |
|            | 104.02 Plans and Working Drawings                                                                         | III – 17 |
|            | 104.03 Conformity with Plans and Specifications                                                           | III – 18 |
|            | 104.04 Coordination of Specifications                                                                     | III – 18 |
|            | 104.05 Cooperation by Contractor                                                                          | III – 19 |
|            | 104.06 Cooperation with Utilities                                                                         | III – 20 |
|            | 104.07 Cooperation Between Contractors                                                                    | III – 21 |
|            | 104.08 Construction Stakes, Lines and Grades                                                              | III – 22 |
|            | 104.09 Authority and Duties of Representatives of the Engineer                                            | III – 22 |
|            | 104.10 Inspection of Work                                                                                 | III – 22 |
|            | 104.11 Removal of Unacceptable and Unauthorized Work                                                      | III – 23 |
|            | 104.12 Load and Speed Restrictions                                                                        | III – 24 |
|            | 104.13 Maintenance During Construction                                                                    | III – 24 |
|            | 104.14 Failure to Maintain the Work                                                                       | III – 25 |
|            | 104.15 Acceptance                                                                                         | III – 25 |
|            | 104.16 Claims for Adjustment                                                                              | III – 26 |
| <b>105</b> | <b>Control of Material</b>                                                                                | III – 27 |
|            | 105.01 Source of Supply and Quality Requirements                                                          | III – 27 |

|            |                                                               |                 |
|------------|---------------------------------------------------------------|-----------------|
| 105.02     | Samples, Tests, Cited Specifications                          | III – 27        |
| 105.03     | Certificates of Compliance                                    | III – 28        |
| 105.04     | Plant Inspection                                              | III – 29        |
| 105.05     | Acceptance of Manufactured Materials                          | III – 30        |
| 105.06     | Storage of Materials                                          | III – 33        |
| 105.07     | Handling Materials                                            | III – 33        |
| 105.08     | Unacceptable Materials                                        | III – 33        |
| 105.09     | Alternates, Substitutions and Contractor's Options            | III – 33        |
| 105.10     | Disposal of Surplus Waste Materials                           | III – 33        |
| <b>106</b> | <b>Legal Relations &amp; Responsibility to the Public</b>     | <b>III – 38</b> |
| 106.01     | Laws to be Observed                                           | III – 38        |
| 106.02     | Permits, Licenses and Taxes (RSA 80-7)                        | III – 41        |
|            | A. Contractors Taxes                                          | III – 42        |
|            | B. Subcontractors Taxes                                       | III – 43        |
|            | C. User's Taxes                                               | III – 43        |
|            | D. Exemption from Attachment                                  | III – 43        |
| 106.03     | Patented Devices, Materials and Processes                     | III – 43        |
| 106.04     | Federal Participation                                         | III – 44        |
| 106.05     | Sanitary, Health and Safety Provisions                        | III – 44        |
| 106.06     | Public Convenience and Safety                                 | III – 45        |
| 106.07     | Railway-Highway Provisions                                    | III – 46        |
| 106.08     | Construction Over or Adjacent to Navigable Waters             | III – 46        |
| 106.09     | Barricades and Warning Signs                                  | III – 47        |
| 106.10     | Use of Explosives                                             | III – 47        |
| 106.11     | Protection and Restoration of Property and Landscape          | III – 48        |
| 106.12     | Responsibility for Damage Claims                              | III – 49        |
| 106.13     | Indemnification and Insurance Requirements                    | III – 49        |
| 106.14     | Use and Occupancy Prior to Acceptance by City                 | III – 51        |
| 106.15     | Contractor's Responsibility for Work                          | III – 51        |
| 106.16     | Contractor's Responsibility for Utility Property and Services | III – 52        |
| 106.17     | Personal Liability of Public Officials                        | III – 53        |
| 106.18     | No Waiver of Legal Rights                                     | III – 53        |
| 106.19     | Environmental Protection                                      | III – 53        |
| 106.20     | No Third Party Beneficiary                                    | III – 54        |
| 106.21     | Civil Rights                                                  | III – 54        |
| 106.22     | Assignment Provision                                          | III – 54        |
| <b>107</b> | <b>Prosecution and Progress</b>                               | <b>III – 55</b> |
| 107.01     | Subletting of Contract                                        | III – 55        |
| 107.02     | Notice to Proceed                                             | III – 56        |

|            |                                                             |                 |
|------------|-------------------------------------------------------------|-----------------|
| 107.03     | Prosecution and Progress                                    | III – 56        |
| 107.04     | Limitation of Operations                                    | III – 57        |
| 107.05     | Character of Employees                                      | III – 57        |
| 107.06     | Methods and Equipment                                       | III – 58        |
| 107.07     | Determination and Extension of Contract Time                | III – 59        |
| 107.08     | Failure to Complete on Time                                 | III – 60        |
| 107.09     | Default of Contract                                         | III – 61        |
| 107.10     | Termination of Contractor's Responsibility                  | III – 62        |
| 107.11     | Guaranty                                                    | III – 62        |
| 108.12     | Understanding of Parties Regarding Department's Performance | III – 63        |
| <b>108</b> | <b>Measurement and Payment</b>                              | <b>III – 64</b> |
| 108.01     | Measurement of Quantities                                   | III – 64        |
| 108.02     | Scope of Payment                                            | III – 66        |
| 108.03     | Compensation for Altered Quantities                         | III – 67        |
| 108.04     | Extra Work                                                  | III – 68        |
|            | a. Labor                                                    | III – 68        |
|            | b. Materials and Specialized Work                           | III – 69        |
|            | c. Equipment                                                | III – 70        |
|            | d. Miscellaneous                                            | III – 71        |
|            | e. Compensation                                             | III – 71        |
|            | f. Statements                                               | III – 71        |
| 108.05     | Eliminated Items                                            | III – 72        |
| 108.06     | Partial Payments                                            | III – 72        |
| 108.07     | Payment for Material on Hand                                | III – 73        |
| 108.08     | Payment for Material Not on Hand                            | III – 74        |
| 108.08     | Semi-final and Final Payments                               | III – 74        |

## **PART IV -- TECHNICAL SPECIFICATIONS**

|     |                                                           |
|-----|-----------------------------------------------------------|
| 201 | Clearing and Grubbing                                     |
| 202 | Removal of Drainage & Sewer Structures                    |
| 203 | Excavation and Embankment                                 |
| 204 | Drilling and Blasting Rock                                |
| 206 | Structure Excavation for Pipes and Other Minor Structures |
| 209 | Bedding & Backfill                                        |
| 214 | Fine Grading                                              |
| 304 | Aggregate Base Course                                     |
| 306 | Reclaimed Stabilized Base                                 |
| 401 | Plant Mix Pavement – General                              |
| 403 | Hot Bituminous Pavement                                   |
| 404 | Pavement Restoration                                      |

|     |                                                          |
|-----|----------------------------------------------------------|
| 410 | Bituminous Surface Treatment                             |
| 411 | Plant Mix Surface Treatment                              |
| 413 | Hot Poured Crack Sealant                                 |
| 417 | Cold Planing of Bituminous Surfaces                      |
| 520 | Portland Cement Concrete                                 |
| 534 | Water Repellent                                          |
| 544 | Reinforcing Steel                                        |
| 570 | Stone Masonry                                            |
| 572 | Stone Wall                                               |
| 583 | Riprap                                                   |
| 585 | Stone Fill                                               |
| 586 | Placing Excavated Rock                                   |
| 593 | Geotextiles                                              |
| 601 | Sanitary Sewers                                          |
| 602 | Sanitary Sewer Manholes                                  |
| 603 | Storm Drains                                             |
| 604 | Catch Basins, Drop Inlets & Drain Manholes               |
| 605 | Underdrains                                              |
| 606 | Guardrail                                                |
| 607 | Fences                                                   |
| 608 | Sidewalks                                                |
| 609 | Curbs                                                    |
| 610 | Driveways                                                |
| 614 | Electrical Conduit                                       |
| 616 | Traffic Signals                                          |
| 618 | Uniformed Officers and Flaggers                          |
| 619 | Maintenance of Traffic                                   |
| 620 | Calcium Chloride                                         |
| 622 | Bounds                                                   |
| 624 | Railroad Protection                                      |
| 628 | Sawed Pavement                                           |
| 629 | Testing of Materials                                     |
| 632 | Reflectorized Pavement Markings                          |
| 641 | Loam                                                     |
| 642 | Limestone                                                |
| 643 | Fertilizer for Grasses                                   |
| 644 | Grass Seed                                               |
| 645 | Erosion Control                                          |
| 646 | Turf Establishment                                       |
| 647 | Humus                                                    |
| 648 | Sod                                                      |
| 650 | Plantings                                                |
| 692 | Mobilization                                             |
| 699 | Temporary Project Water Pollution Control (Soil Erosion) |
| 702 | Bituminous Materials                                     |
| 703 | Aggregates                                               |

|     |                                                 |
|-----|-------------------------------------------------|
| 707 | Cement Mortar                                   |
| 708 | Paints                                          |
| 711 | Preformed Retroreflective Pavement Marking Tape |
| 718 | Reflective Sheeting                             |

## LIST OF FIGURES

### Figure No.

|          |                                                                                        |
|----------|----------------------------------------------------------------------------------------|
| II, 2-1  | Typical Roadway Section                                                                |
| II, 2-2  | Typical Cul-de-Sac                                                                     |
| II, 2-3  | Typical Temporary Turnaround                                                           |
| II, 5-1  | Patching Guidelines                                                                    |
| II, 5-2  | Pavement Restoration (Permanent Pavement Repair)                                       |
| II, 5-3  | Pavement Restoration (Temporary Pavement Repair)                                       |
| II, 5-4  | Pavement Restoration (Concrete/Cobblestones)                                           |
| II, 5-5  | Sidewalk/Shoulder Restoration                                                          |
| II, 6-1  | Sample Certificate of Compliance                                                       |
| 206-1    | Unsuitable Excavation                                                                  |
| 209-1    | Excavation Pay Limits for Trenches                                                     |
| 601-1    | Typical Sewer Trench Detail                                                            |
| 601-2    | Typical Sewer Connection                                                               |
| 601-3    | Typical Sewer Service Cleanout                                                         |
| 601-4    | Inside Drop Connection for PVC Pipe                                                    |
| 601-5    | Strap Detail for Inside Drop Connection                                                |
| 601-6    | Service Chimney for PVC Pipe                                                           |
| 602-1    | Precast Reinforced Concrete Sanitary Sewer Manhole                                     |
| 602-2    | Manhole Joint Sleeve                                                                   |
| 602-3    | Gas Trap                                                                               |
| 602-4    | Grease Trap                                                                            |
| 603-1    | Concrete & Mortar Rubble Masonry Headwall for R.C. Pipe                                |
| 603-2    | Concrete Headwall With 45 degree Wings for R.C. Pipe                                   |
| 603-3    | Mortar Rubble Masonry Headwalls With 45 degree Wings for R.C. Pipe                     |
| 603-4    | Concrete Headwalls With 45 degree Wings for R.C. Pipe                                  |
| 603-5    | Mortar Rubble Masonry Headwalls With 45 degree Wings for Twin R.C. Pipe (Plate 1 of 2) |
| 603-6    | Mortar Rubble Masonry Headwalls With 45 degree Wings for Twin R.C. Pipe (Plate 2 of 2) |
| 603-7    | Slope Rounding at Top of Culvert Headwalls                                             |
| 603-8a,b | Protection Grate for Pipe Outlets                                                      |
| 604-1    | Precast Reinforced Concrete Drain Manhole                                              |
| 604-2    | Precast Reinforced Concrete Catch Basin & Drop Inlet                                   |
| 604-3    | Standard Grate & Frame Type A                                                          |
| 604-4    | Standard Grate & Frame Type B                                                          |
| 604-5    | Standard Type C Top                                                                    |
| 604-6    | Standard Grate & Frame Type E                                                          |
| 604-7    | Standard Grate & Frame Type F                                                          |
| 604-8    | Standard Grate & Frame Type B, Alt. 1                                                  |

|           |                                                           |
|-----------|-----------------------------------------------------------|
| 604-9     | Standard Grate & Frame Type E, Alt. 1                     |
| 604-10    | Rectangular slabs A                                       |
| 604-11    | Rectangular slabs B                                       |
| 605-1     | Underdrain Headwalls                                      |
| 606-1     | Beam Guard Rail – Standard Section                        |
| 606-2     | Beam Guard Rail – Terminal Unit F                         |
| 606-3     | Beam Guard Rail – Bridge Approach Unit                    |
| 606-4     | Beam Guard Rail -- Terminal Unit Type G                   |
| 606-5 a,b | Beam Guard Rail -- Elevation Views                        |
| 606-6     | Beam Guard Rail -- Bolt Slots & Plate Washer              |
| 606-7     | Beam Guard Rail -- Bolt Details                           |
| 606-8     | Beam Guard Rail -- Section Thru Rail Element              |
| 606-9     | Beam Guard Rail -- F Unit Anchor Detail                   |
| 606-10    | Beam Guard Rail -- F Unit End Section Detail              |
| 606-11    | Beam Guard Rail -- F Unit Anchor Setting                  |
| 606-12    | Beam Guard Rail -- End Section Detail                     |
| 606-13    | Beam Guard Rail -- Bridge End Shoe Detail                 |
| 607-1     | Chain Link Fence -- General Details                       |
| 607-2     | Chain Link Fence -- Post Assemblies                       |
| 607-3     | Chain Link Fence -- Post Footing Details                  |
| 607-4     | Chain Link Fence -- Post & Brake Dimensions               |
| 607-5     | Woven Wire Fence -- General Details                       |
| 607-6     | Woven Wire Fence -- Bracing Details                       |
| 607-7     | Woven Wire Fence -- Wire Fastening Details                |
| 607-8     | Woven Wire Fence -- Typical Fenced Post Assembly          |
| 608-1     | Bituminous Sidewalk Detail                                |
| 608-2     | Concrete Sidewalk Detail                                  |
| 608-3     | Brick Sidewalk Detail                                     |
| 608-4     | Concrete Sidewalk With Brick Accent Detail                |
| 608-5     | Corner Sidewalk Ramp                                      |
| 608-6     | Typical Sidewalk Ramp                                     |
| 609-1     | Granite Curb Details                                      |
| 609-2     | Granite Slope Curb Details                                |
| 609-3     | Cutting Straight Granite Slope Curb With Radial Joints    |
| 609-4     | Granite Curb Inlets                                       |
| 609-5     | Bituminous Concrete Curb                                  |
| 610-1     | Typical Driveway Profile                                  |
| 610-2     | Typical Residential Drive                                 |
| 610-3     | Bituminous Drive Typical Section                          |
| 610-4     | Concrete Drive Typical Section                            |
| 614-1     | Conduit Details                                           |
| 614-2     | Pull Box Frame & Cover                                    |
| 614-3 a,b | Detector Box Details                                      |
| 616-1     | Concrete Foundation for Standard Traffic Signal Post      |
| 616-2     | Concrete Foundation for Standard Control Cabinet          |
| 616-3     | Standard Round Traffic Signal Foundation Plan & Elevation |

|        |                                                                         |
|--------|-------------------------------------------------------------------------|
| 616-4a | Standard Round Traffic Signal Foundation Reinforcing Steel Schedule     |
| 616-4b | Standard Round Traffic Signal Foundation Typical Quantities Per<br>Base |
| 616-4c | Standard Round Traffic Signal Foundation Size Determination Chart       |
| 616-4d | Standard Round Traffic Signal Foundation General Notes                  |
| 622-1  | Concrete Bound Detail – 1                                               |
| 622-2  | Concrete Bound Detail – 2                                               |
| 699-1  | Erosion Protection Type A                                               |
| 699-2  | Erosion Protection Type B                                               |
| 699-3  | Erosion Protection Type C                                               |
| 699-4  | Erosion Protection Type D                                               |
| 699-5  | Erosion Protection Type E                                               |
| 699-6  | Silt Fence Detail                                                       |
| 699-7  | Sedimentation Control at Catch Basin                                    |
| 699-8  | Sediment Control Bag for Catch Basin                                    |
| 699-9  | Block and Gravel Sedimentation Control Inlet                            |
| 699-10 | Riprap Swale Detail                                                     |
| 699-11 | Haybale Check Dam                                                       |
| 699-12 | Level Spreader Detail                                                   |